SAMPLE BoQ for estimating only

Project	Proposed 4-Bedroom Duplex with BQ
Location	Plot 14 (sample), Lekki Phase 1, Lagos
Client	Mrs A. Okafor (sample)
Contractor	Emmy Builders Ltd (sample)
Consultant	Bisi Adeyemi & Partners (sample)

Bill	2	Substructure			
Item	Description	Unit	Qty	Rate	Amount
2.1	Excavate foundation trench not exceeding 1.50 m deep starting from stripped level	m3	48.6	6500.00	315900.00
2.2	50 mm thick plain concrete blinding (1:3:6) under strip footings	m2	72	3800.00	273600.00
2.3	Plain in-situ concrete (1:2:4 - 19 mm aggregate) in strip footings	m3	21.6	145000.00	3132000.00
2.4	225 mm sandcrete hollow blockwork in foundation filled solid with concrete up to DPC	m2	118	14500.00	1711000.00
2.5	Hardcore filling, well rammed and consolidated, in 150 mm layers	m2	186	4200.00	781200.00
2.6	Anti-termite treatment to surface of hardcore (approved chemical)	m2	186	950.00	176700.00
2.7	1000-gauge polythene damp-proof membrane, 150 mm laps	m2	186	650.00	120900.00
2.8	150 mm reinforced concrete (1:2:4) ground floor oversite slab	m3	27.9	145000.00	4045500.00
	Carried to Summary				10556800.00

Bill	3	Ground Floor Frame			
Item	Description	Unit	Qty	Rate	Amount
3.1	Reinforced concrete (1:2:4) in columns and beams	m3	14.4	165000.00	2376000.00
3.2	High-yield steel reinforcement, Y12-Y16, cut, bent and fixed	kg	1850	1450.00	2682500.00
3.3	Sawn formwork to sides and soffits of columns and beams	m2	96	4800.00	460800.00
3.4	225 x 225 mm reinforced concrete lintel over openings	m	25	12000.00	300000.00
	Carried to Summary				5819300.00

Bill	1	Preliminaries			
Item	Description	Unit	Qty	Rate	Amount
1.1	Preliminaries	sum	1	2500000.00	2500000.00
	Carried to Summary				2500000.00

Bill	4	Upper Floor (slab columns blockwork)			
Item	Description	Unit	Qty	Rate	Amount
4.1	Upper floor slab columns and blockwork	sum	1	9800000.00	9800000.00
	Carried to Summary				9800000.00

Bill	6	Finishes			
Item	Description	Unit	Qty	Rate	Amount
6.1	Finishes	sum	1	7450000.00	7450000.00
	Carried to Summary				7450000.00

Bill	5	Roofing			
Item	Description	Unit	Qty	Rate	Amount
5.1	Roofing	sum	1	6200000.00	6200000.00
	Carried to Summary				6200000.00

Bill	7	Electrical & Plumbing Services			
Item	Description	Unit	Qty	Rate	Amount
7.1	Electrical and plumbing services	sum	1	3900000.00	3900000.00
	Carried to Summary				3900000.00

Bill	8	External Works			
Item	Description	Unit	Qty	Rate	Amount
8.1	External works	sum	1	1773900.00	1773900.00
	Carried to Summary				1773900.00

General Summary

Bill	Description	Amount
1	Preliminaries	2500000.00
2	Substructure	10556800.00
3	Ground Floor Frame	5819300.00
4	Upper Floor (slab columns blockwork)	9800000.00
5	Roofing	6200000.00
6	Finishes	7450000.00
7	Electrical & Plumbing Services	3900000.00
8	External Works	1773900.00
	Sub-total	48000000.00

	Provisional Sum (soakaway & septic tank)	1000000.00
	Contingency (5% of sub-total)	2400000.00
	Total before VAT	51400000.00
	VAT @ 7.5%	3855000.00
	CONTRACT SUM	55255000.00
Note	Retention: 5% of each interim payment, half released at practical completion and	
Note	Mobilisation advance: nil.	
Note	Payment within 14 days of certificate.	
Note	Liquidated damages: N50,000 per week, capped at 10% of the contract sum.	
Note	Commencement 3 Nov 2026; completion 28 Aug 2027.	